

COEP Technological University

A Unitary Public University of Government of Maharashtra

(Formerly College of Engineering Pune)

Wellesley Road, Shivajinagar, Pune-411005, Maharashtra, India

Invitation of Quotations for

**Electrical Work for Toilet & Bathroom, 4Nos Rooms and Charging
Point Wiring at Hostel Campus, COEP Tech. University, Pune.**


Ref: COEP TECH/EWC/ Electrical Work /2026-27/98 Date: 07/08/2026

Website: <https://www.coeptech.ac.in>

Telephone Number: - 020 - 2550 - 7409

Contact Person: 1. Dr. A. R. Phadke - 020 - 2550 - 7409

2. Mr. Rizwan Inamdar



COEP Technological University

A Unitary Public University of Government of Maharashtra
(Formerly College of Engineering Pune)
Wellesley Road, Shivajinagar, Pune-411005, Maharashtra, India

Ref: COEP TECH/ EWC/Electrical Work. /2026-27/98

Dated: 07/08/2026

INVITATION OF QUOTATION

Name of Work: Electrical Work for Toilet & Bathroom, Rooms and Charging Point Wiring at Hostel Campus, COEP Tech. University, Pune.

Dear Sir,

You are invited to submit your most competitive quotation for the **above work**. The details are as below:

Sr.No	Description	Unit	Quantity	Rate	Amount in Rs
1	Supplying, erecting & marking DPMCB 6A to 32A, C-series with rated short-circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-MCB	Nos.	4		
2	Supplying, erecting & marking SPMCB 6A to 32A ,C-series with rated short-circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-MCB	Nos.	16		

3	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places. as per specification no. WG-MA/BW. NOTE.Rates of earth wire shall be calculated as one half rate of mains of bunch of two wire. Make-Polycab Optima Plus .	Mtr.	498		
4	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places as per specification no. WG-MA/BW. NOTE. Rates of earth wire shall be calculated as one half rate of mains of bunch of two wire. Make- Polycab Optima Plus.	Mtr.	448		
5	Supplying & erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places. as per specification no. WG-MA/BW.. NOTE Double the rate of two wire bunch for calculating rate of four wire bunch upto 10 sq.mm. Make -Polycab Optima Plus. Note-Rates of earth wire shall be calculated as one half rate of mains of bunch of two wire.	Mtr.	35		

6	Supplying & erecting HMS PVC conduit 32mm dia. with necessary accessories in wall/floor with chiselling appropriately as per specification no. WG-MA/CC.	Mtr.	100		
7	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25mm with accessories on wall/ceiling as per specification no. WG-MA/CON.	Mtr.	195		
8	Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 6 ways (6 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame as per specification no. SW-MCBDB	Nos.	2		
9	2-way (2-Pole) MCB Encloser Box. Make Legrand.	Nos.	2		
10	Supplying and erecting PVC Surface modular switch box with double mounting plate for 1 module complete.	Nos.	2		
11	Supplying and erecting PVC Surface modular switch box with double mounting plate for 2 module complete	Nos.	2		
12	Supplying and erecting PVC Surface modular switch box with double mounting plate for 3 module complete.	Nos.	30		
13	Supplying and erecting PVC Surface modular switch box with double mounting plate for 4 module complete.	Nos.	2		

14	Supplying and erecting PVC Surface modular switch box with double mounting plate for 6 module complete.	Nos.	38		
15	Supplying and erecting PVC Surface modular switch box with double mounting plate for 16/18 module complete.	Nos.	1		
16	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 module complete. Make - Legrand Mylinc	Nos.	12		
17	Supplying and erecting modular type switch 6A/ 10A on provided plate and box with wiring connections complete. Make- Legrand Mylinc	Nos.	234		
18	Supplying and erecting modular type switch 16A on provided plate and box with wiring connections complete. Make- Legrand Mylinc	Nos.	3		
19	Supplying and erecting modular type 3 pin 6A multi socket with safety shutter on provided plate and box with wiring connections complete. Make - Legrand Mylinc	Nos.	108		
20	Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring connections complete. Make- Legrand Mylinc	Nos.	3		

21	Supplying and erecting anodized aluminium light LED fitting (4 feet) Max. 22W with high transitivity diffuser with system lumens output of Min.2200 lumens , min. efficacy of 100 lumen/W, CRI>80, CCT upto 6000K, Beam Angle of 110 deg., Ripple0.95, operating range of 200-270V, surge protection of 2 kV, Life class of 50,000 Hrs at L70B50 including driver with end caps on provided PVC Block/wooded board with minimum 2 years warranty as per specification No. FG-IDF/LED.	Nos.	34		
22	Supplying and erecting anodized aluminium mirror light LED fitting (2 feet) Max. 12W with high transitivity diffuser with min. system lumens output of 1200 lumens, min. efficacy of 100 lumen/W, CRI>80, CCT upto 6000K, Beam Angle of 110 deg., Ripple0.95, operating range of 200-270V, surge protection of 2 kV, Life class of 50,000 Hrs at L70B50 including driver with end caps on provided PVC Block / wooded board with minimum 2 years warranty as per specification No. FG-IDF/LED.	Nos.	52		

23	Point wiring for light/bell/exhaust fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification no. WG-PW/SW	Nos.	135		
24	Supplying and erecting exhaust fan medium duty 230 V A.C. 50 cycles 150/225 mm. 1400 RPM with condenser complete erected in position with necessary materials. Fan motor with moisture proof treatment and 'E' class insulation.	Nos.	38		
25	Supplying & erecting HMS PVC conduit 25mm dia. with necessary accessories in wall/floor with chiselling appropriately as per specification no. WG-MA/CC.	Mtr.	55		
26	Supplying and erecting Energy Saving Ceiling fan of 3 star rating as per BEE 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	Nos.	5		
27	Supplying & fixing anchor type fastener fan hook, with 2 nos. of 10 mm dia x 75 mm long with necessary materials for ceiling fan.	Nos.	6		

28	supplying and erecting modular type (two module) electronic step regulator for fan, on provided plate and box with wiring connections complete. Make- Legrand Mylinc	Nos.	6		
29	Point wiring for ceiling fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification no. WG-PW/SW NOTE:- In case length of point wiring exceeds 6 meters, add 10% of rate, for every additional length of 1 meter or part thereof.	Nos.	6		
30	Supplying and erecting exhaust fan heavy duty 230 V A.C. 50 cycles 450 mm. 1400 RPM complete erected in position as per specification no. FG-FN/EXF	Nos.	1		
31	Supplying and erecting 'B' grade G.I. pipe / M.S. pipe down rod duly painted for fan complete erected with PVC three core flexible cable 1 sq. mm copper PVC wire.	mtr.	6		

32	Supplying and erecting mains with WP 3 x 6 sq. mm. 1.1kV. grade aluminium PVC insulated and PVC sheathed wires on G.I. bearer wire no. 8 SWG complete erected with required size of porcelain reel insulators and 16 SWG G.I. binding wire	mtr.	35		
	Basic Amount (Rs)				
	Add for GST @18% (Rs)				
	Gross total amount in (Rs)				

Terms and Conditions:

1. The bidder should attach the required document with the tender.
2. The bidder should submit GST registration document along with tender.

3. Special Conditions for the work:

- a. COEP Technological University, Pune is not liable for any breach of any Government rules/regulations by Bidder/agency/firm or its employees. The Bidder/agency/firm will be solely responsible for their action.
- b. If during work within the premises of COEP Technological University, Pune any mishap/accident occurs causing injuries to the employees or representatives of Bidder/agency/firm, necessary compensation as required by the statute will be borne by Bidder/agency/firm itself, and COEP Technological University, Pune is not responsible against all claims on such accounts.
- c. All the staff deployed by Bidder/agency/firm will ensure that they are polite and courteous in their behavior. They shall carry their photo identity card prominently displayed during the repairing hours.
- d. The bidder / agency / firm should be prepared to come to COEP Technological University, Pune to take part in the discussion, if required in this regard.

- e. All work shall be carried out with due regard to the convenience of COEP Technological University, Pune. The orders of the concerned authority shall be strictly observed.
- 5. The taxes, insurance, freight, packing and forwarding charges if any must be quoted in Indian Rupees separately.
- 6. The rates shall be valid for 90 days.
- 7. Quotation(s) received after the last date of Quotation submission will be rejected.
- 8. All following documents/certificates should be provided / attached.
 - a) Shop Act License/Incorporation Certificate/Firm Registration Certificate Copy.
 - b) PAN Card Copy c) GST Certificate Copy
- 9. All duties, taxes, and other levies payable by the bidder need to be included in the total price and break up needs to be indicated.
- 10. The bidder shall have to quote for all the items of the quotations. Part quotations/incomplete quotations shall be summarily rejected without any consideration.
- 11. The quotations shall be signed by an authorized person and the bidder's full name and status be indicated below the signature along with an official stamp of the vendor/firm/company.
- 12. Offers in the bid should be written in English and price should be written in both figures and words.
- 13. The supply/work should be completed within 2 weeks from the date of Work order.
- 14. No extension shall be given for supply/work/service. In such a case a penalty for delay in proportion to the cost of equipment/work/service. at the rate of 0.5 % per week; maximum limit of 10% shall be charged in case of PO value is less than 2 Lakh.
 - a. **In case of delay more than 2 weeks, beyond the stipulated complication of work date, order shall be deemed cancelled.**
 - b. Bidder shall be responsible for successful Installation, Commissioning and testing of the supplied devices at defined locations
- 15. The 100% bill for the above work will be paid immediately after successful commissioning and testing of the work. No advance payment will be given.
- 16. The COEP Technological University reserves the right to cancel any of the items of the tender without any reason thereof.
- 17. The quotations should be downloaded from the COEP Technological University website <https://www.coeptech.ac.in/> tenders and submitted in the format given

above to Electrical Engineering Department, COEP Technological University Pune during working days.

18. The quotation should be duly signed and addressed to **The Vice Chancellor, COEP Technological University, Pune-5** and submitted in sealed envelope.
19. Quotations will not be received by E-mail / FAX.
20. The various time limits are as follows.

Activity	Date	Time
Start of submission of quotation	07/08/2026	11.00 am
Last date of submission of quotation	12/08/2026	04.00 pm
Opening of Quotations	13/08/2026	04.00 pm

Sd
Registrar
COEP Technological University, Pune.